RUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/22/2020-21, Date:17.11.2020

SCHEDULE-B

NAME OF WORK: Solid Waste Management in Dasarahalli ward no 15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri K S RAMESH	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	99.75	135.0	Rupees One Hundred Thirty Five Only
2	Supplying fixing precast reinforement concrete slabs 10cm thick including cost of reinforecemet as per design and drawing material cost transpotation hire charges of machinery. Machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	259.20	1500.0	Rupees One Thousand Five Hundred Only
3	Supplying of the labour on daily rate basis to the require place etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Day	100.00	446.0	Rupees Four Hundred Forty Six Only
4	Disposal of debris to the final place of disposal with all lead and lift and as directions by the Engineer incharge of work. KSRRB M100-1 Loading and Unloading of Stone Boulder I Stone Cum 57.00 aggregates /Sand/ Kanker I Moorum. KSRRB M100-1: Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	99.75	80.0	Rupees Eighty Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,